Project: **FPM Spice Extension Improvement**
Location: **E24PV+M3G, Bulihan, Malvar, Batangas**
Attention **Ms. Marycel Buendia**
QTE Ref **QTE-26-001-EM**
Date **January 05,2026**

COST		**1.75**		**1.25**
	1.15	**1.75**		**35%**

Item	Description	Qty	Unit	Unit Cost (Php)				Total Amount (Php)
				Material	Total	Labor	Total	
I.	**General Requirements**					0.40		
	Mobilization and Demobilization	1	lot			20,000.00	20,000.00	20,000.00
	PPE and other Safety & Security Requirements							
	Safety Officer	1	lot			16,000.00	16,000.00	16,000.00
	Warning and Hazzard Signs, Tarpaulins, etc.	1	lot	3,000.00	**3,000.00**		-	3,000.00
	PPE	1	lot				-	-
	Cleaning and Housekeeping	1	lot			5,000.00	5,000.00	5,000.00
	Site Supervisory and Administrative Staff	1	lot			22,000.00	22,000.00	22,000.00
	Field and Operations General Expenses incl Equipment Cost	1	lot	15,000.00	15,000.00			15,000.00
	Scaffolding Works	1	lot		-	5,000.00	5,000.00	5,000.00
	Sub Total:							**86,000.00**
II.	**DIRECT COST**							
	OLD RESTROOM CONVERSION TO STOCK ROOM							
	DISMANTLING AND DEMOLITION				-		-	
	Removal of CHB wall (Inner and Outer Wall)	8.31	sqm		-	300.00	2,493.00	2,493.00
	Removal of Existing wall and Floor tiles	24.08	sqm		-	250.00	6,020.00	6,020.00
	Removal of Existing Ceiling	7.28	sqm		-	200.00	1,456.00	1,456.00
	Termination of Existing Waterline connections (includes installation of 1 isolation valve)	1.00	lot	1,000.00	1,000.00	2,500.00	2,500.00	3,500.00
	CONCRETE AND MASONRY WORKS				-	-	-	-
	Wall Plaster Finish	16.80	sqm	300.00	5,040.00	210.00	3,528.00	8,568.00
	Concrete Floor Slab				-	-	-	-
	Class A Concrete Mix	0.87	cu.m	6,500.00	5,655.00	10,000.00	8,700.00	14,355.00
	10mm RCB (30 cm spaced OC both ways)	15.00	pcs	140.00	2,100.00	98.00	1,470.00	3,570.00
	Tie Wire	1.00	kg	100.00	100.00	50.00	50.00	150.00
	CEILING				-	-	-	-
	Ceiling Installation (1/4" thk Ficem Board, Metal framing)	16.80	sqm	500.00	8,400.00	350.00	5,880.00	14,280.00
	PAINTING WORKS (2 COATINGS)				-	-	-	-
	Walls	33.75	sqm		-	300.00	10,125.00	10,125.00
	Skimcoat	5.00	bags	550.00	2,750.00		-	2,750.00
	Flat Latex	1.00	tin	3,000.00	3,000.00		-	3,000.00
	Semi Gloss topcoat	1.00	tin	3,300.00	3,300.00		-	3,300.00
	Ceiling	7.28	sqm		-	300.00	2,184.00	2,184.00
	Flat Latex	1.00	gal	1,000.00	1,000.00		-	1,000.00
	Semi Gloss topcoat	1.00	gal	1,100.00	1,100.00		-	1,100.00
	Skimcoat	1.00	bags	550.00	550.00		-	550.00

Project: **FPM Spice Extension Improvement**
Location: **E24PV+M3G, Bulihan, Malvar, Batangas**
Attention **Ms. Marycel Buendia**
QTE Ref **QTE-26-001-EM**
Date **January 05,2026**

COST		**1.75**	**1.25**
	1.15	**1.75**	**35%**

Item	Description	Qty	Unit	Unit Cost (Php)				Total Amount (Php)
				Material	Total	Labor	Total	
	Consumables (paint brush, Sand paper, Roller Brush, Mesh tape, etc)	1.00	lot	3,000.00	3,000.00		-	3,000.00
	CONCRETE ZOCALO WALL							
	Installation of Concrete Zocalo (60 cm high) Including Granite tiles	13.70	lm			4,500.00	61,650.00	61,650.00
	Phenlic 3/4"	7.00	pcs	1,250.00	8,750.00			8,750.00
	Cocolumber 2x3x10 ft	35.00	pcs	199.00	6,965.00			6,965.00
	Class A Concrete Mix	1.25	cu.m	6,500.00	8,125.00			8,125.00
	12mm RSB	15.00	pcs	250.00	3,750.00			3,750.00
	Tie Wire	3.00	kgs	100.00	300.00			300.00
	60x60 3/4" thk Granite Tiles (Salt and pepper)	25.00	pcs	1,500.00	37,500.00			37,500.00
	Adhesive	5.00	bags	300.00	1,500.00			1,500.00
	Grout	1.00	bags	180.00	180.00			180.00
	Consumables (Nails, etc)	1.00	lot	2,000.00	2,000.00			2,000.00
	BOLLARD INSTALLATION							
	Supply and Installation of Inner Bollards (80cm high 4" S40 GI Pipe on 10mm Baseplate) (concrete filled)	2.00	units		-	2,500.00	5,000.00	5,000.00
	4" S40 GI Pipe	1.00	pcs	4,650.00	4,650.00		-	4,650.00
	150x150x10mm Base Plate	2.00	pcs	1,500.00	3,000.00		-	3,000.00
	20mm Anchor Bolts	4.00	pcs	500.00	2,000.00		-	2,000.00
	Coring Works 4" by 20cm depth	2.00	units	1,200.00	2,400.00		-	2,400.00
	Supply and Installation of Outer Bollard (Arch Style)	1.00	units		-	15,000.00	15,000.00	15,000.00
	4" S40 GI Pipe	3.00	pcs	4,650.00	13,950.00		-	13,950.00
	Coring Works 4" by 45cm depth	4.00	units	1,200.00	4,800.00		-	4,800.00
	Epoxy Primer Black	1.00	gal	1,300.00	1,300.00		-	1,300.00

Project: **FPM Spice Extension Improvement**
Location: **E24PV+M3G, Bulihan, Malvar, Batangas**
Attention **Ms. Marycel Buendia**
QTE Ref **QTE-26-001-EM**
Date **January 05,2026**

COST		**1.75**	**1.25**
	1.15	**1.75**	**35%**

Item	Description	Qty	Unit	Unit Cost (Php)				Total Amount (Php)
				Material	Total	Labor	Total	
	QDE Yellow	1.00	gal	1,100.00	1,100.00		-	1,100.00
	QDE Black	1.00	gal	1,100.00	1,100.00		-	1,100.00
	Consumables (Paint brush, Masking Tape, Welding Rods, Cutting Disc, etc)	1.00	lot	5,000.00	5,000.00		-	5,000.00
	Sub Total:							**271,421.00**
	TOTAL AMOUNT							357,421.00
	12% VAT :							42,890.52
TOTAL PROJECT COST(VAT INCLUDED) :								**PHP 400,311.52**

Prepared By:

Rommel Antonio
Operation Head

Noted By:

Rey R. Araos
President