Our Ref. **QTE-26-001-EM**

Date: **January 05,2026**

CDO Malvar, Batangas
E24PV+M3G, Bulihan, Malvar, Batangas

Attention: **: MARYCEL BUENDIA**
Corporate Purchasing

Subject: **FPM Spice Extension Improvement**

Gentlemen:

In response to your inquiry, we are pleased to quote you the following items:

ITEM	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL AMOUNT
1	Supply of quality labor, materials, tools and equipment for the above mentioned subject with itemized price breakdown indicated in the attachment.	1	lot	541,933.73	541,933.73
Total Project Amount (VAT Included)					**PHP 541,933.73**

TERMS AND CONDITIONS:

Completion : To be agred upon

Payment : Thirty Percent (30%) Down Payment, Sixty Percent (60%) Progress Billing and Ten Percent (10%) Retention

Validity : Forty Five (45) Days

: Eyelectric, Incorporated reserves the right to modify the price in case of materials and logistics changes in the market due to extraneous and supervening events

EXCLUSIONS:

1.) All other scope not specifically mentioned in this proposal.

2.) The owner shall provide ample space for the contractor for storage of materials.

3.) If so required, COVID19 related testing, vaccine & treatment are excluded. Though rapid test included.

4.) Permitting are not included in this proposal.

Thank you very much for giving EYELECTRIC, INCORPORATED the opportunity to quote on this requirements. We hope everything is in order. We will keep in touch as to the development of your inquiries.

Very truly yours,

EYELECTRIC, INC.

Rommel Antonio
Operation Head

Noted by:

Rey R. Araos
President

Project: **FPM Spice Extension Improvement**
Location: **E24PV+M3G, Bulihan, Malvar, Batangas**
Attention **Ms. Marycel Buendia**
QTE Ref **QTE-26-001-EM**
Date **January 05,2026**

Item	Description	Qty	Unit	Unit Cost (Php)				Total Amount (Php)
				Material	Total	Labor	Total	
I.	**General Requirements**							
	Mobilization and Demobilization	1	lot			23,000.00	23,000.00	23,000.00
	PPE and other Safety & Security Requirements							
	Safety Officer	1	lot			18,400.00	18,400.00	18,400.00
	Warning and Hazzard Signs, Tarpaulins, etc.	1	lot	4,200.00	4,200.00	-	-	4,200.00
	PPE	1	lot			-	-	-
	Cleaning and Housekeeping	1	lot			5,750.00	5,750.00	5,750.00
	Site Supervisory and Administrative Staff	1	lot			25,300.00	25,300.00	25,300.00
	Field and Operations General Expenses incl Equipment Cost	1	lot	21,000.00	21,000.00	-	-	21,000.00
	Scaffolding Works	1	lot	-	-	7,000.00	7,000.00	7,000.00
			Sub Total:					**104,650.00**
II.	**DIRECT COST**							
	OLD RESTROOM CONVERSION TO STOCK ROOM							
	DISMANTLING AND DEMOLITION				-		-	
	Removal of CHB wall (Inner and Outer Wall)	8.31	sqm	-	-	420.00	3,490.20	3,490.20
	Removal of Existing wall and Floor tiles	24.08	sqm	-	-	350.00	8,428.00	8,428.00
	Removal of Existing Ceiling	7.28	sqm	-	-	280.00	2,038.40	2,038.40
	Termination of Existing Waterline connections (includes installation of 1 isolation valve)	1.00	lot	1,400.00	1,400.00	3,500.00	3,500.00	4,900.00
	CONCRETE AND MASONRY WORKS			-	-	-	-	-
	Wall Plaster Finish	16.80	sqm	420.00	7,056.00	294.00	4,939.20	11,995.20
	Concrete Floor Slab			-	-	-	-	-
	Class A Concrete Mix	0.87	cu.m	9,100.00	7,917.00	14,000.00	12,180.00	20,097.00
	10mm RCB (30 cm spaced OC both ways)	15.00	pcs	196.00	2,940.00	137.20	2,058.00	4,998.00
	Tie Wire	1.00	kg	140.00	140.00	70.00	70.00	210.00
	CEILING			-	-	-	-	-
	Ceiling Installation (1/4" thk Ficem Board, Metal framing)	16.80	sqm	700.00	11,760.00	490.00	8,232.00	19,992.00
	PAINTING WORKS (2 COATINGS)			-	-	-	-	-
	Walls	33.75	sqm	-	-	420.00	14,175.00	14,175.00
	Skimcoat	5.00	bags	770.00	3,850.00	-	-	3,850.00
	Flat Latex	1.00	tin	4,200.00	4,200.00	-	-	4,200.00
	Semi Gloss topcoat	1.00	tin	4,620.00	4,620.00	-	-	4,620.00
	Ceiling	7.28	sqm	-	-	420.00	3,057.60	3,057.60
	Flat Latex	1.00	gal	1,400.00	1,400.00	-	-	1,400.00
	Semi Gloss topcoat	1.00	gal	1,540.00	1,540.00	-	-	1,540.00
	Skimcoat	1.00	bags	770.00	-		-	-

Project: **FPM Spice Extension Improvement**
Location: **E24PV+M3G, Bulihan, Malvar, Batangas**
Attention **Ms. Marycel Buendia**
QTE Ref **QTE-26-001-EM**
Date **January 05,2026**

Item	Description	Qty	Unit	Unit Cost (Php)				Total Amount (Php)
				Material	Total	Labor	Total	
	Consumables (paint brush, Sand paper, Roller Brush, Mesh tape, etc)	1.00	lot	4,200.00	4,200.00	-	-	4,200.00
	CONCRETE ZOCALO WALL			-	-	-	-	-
	Installation of Concrete Zocalo (60 cm high) Including Granite tiles	13.70	lm	-	-	6,300.00	86,310.00	86,310.00
	Phenlic 3/4"	7.00	pcs	1,750.00	12,250.00	-	-	12,250.00
	Cocolumber 2x3x10 ft	35.00	pcs	278.60	9,751.00	-	-	9,751.00
	Class A Concrete Mix	1.25	cu.m	9,100.00	11,375.00	-	-	11,375.00
	12mm RSB	15.00	pcs	350.00	5,250.00	-	-	5,250.00
	Tie Wire	3.00	kgs	140.00	420.00	-	-	420.00
	60x60 3/4" thk Granite Tiles (Salt and pepper)	25.00	pcs	2,100.00	52,500.00	-	-	52,500.00
	Adhesive	5.00	bags	420.00	2,100.00	-	-	2,100.00
	Grout	1.00	bags	252.00	252.00	-	-	252.00
	Consumables (Nails, etc)	1.00	lot	2,800.00	2,800.00	-	-	2,800.00
	BOLLARD INSTALLATION			-	-	-	-	-
	Supply and Installation of Inner Bollards (80cm high 4" S40 GI Pipe on 10mm Baseplate) (concrete filled)	2.00	units	-	-	3,500.00	7,000.00	7,000.00
	4" S40 GI Pipe	1.00	pcs	6,510.00	6,510.00	-	-	6,510.00
	150x150x10mm Base Plate	2.00	pcs	2,100.00	4,200.00	-	-	4,200.00
	20mm Anchor Bolts	4.00	pcs	700.00	2,800.00	-	-	2,800.00
	Coring Works 4" by 20cm depth	2.00	units	1,680.00	3,360.00	-	-	3,360.00
	Supply and Installation of Outer Bollard (Arch Style)	1.00	units	-	-	21,000.00	21,000.00	21,000.00
	4" S40 GI Pipe	3.00	pcs	6,510.00	19,530.00	-	-	19,530.00
	Coring Works 4" by 45cm depth	4.00	units	1,680.00	6,720.00	-	-	6,720.00
	Epoxy Primer Black	1.00	gal	1,820.00	1,820.00	-	-	1,820.00

Project: **FPM Spice Extension Improvement**
Location: **E24PV+M3G, Bulihan, Malvar, Batangas**
Attention **Ms. Marycel Buendia**
QTE Ref **QTE-26-001-EM**
Date **January 05,2026**

Item	Description	Qty	Unit	Unit Cost (Php)				Total Amount (Php)
				Material	Total	Labor	Total	
	QDE Yellow	1.00	gal	1,540.00	1,540.00	-	-	1,540.00
	QDE Black	1.00	gal	1,540.00	1,540.00	-	-	1,540.00
	Consumables (Paint brush, Masking Tape, Welding Rods, Cutting Disc, etc)	1.00	lot	7,000.00	7,000.00	-	-	7,000.00
	Sub Total:							**379,219.40**
	TOTAL AMOUNT							483,869.40
	12% VAT :							58,064.33
TOTAL PROJECT COST(VAT INCLUDED) :								**PHP 541,933.73**

Prepared By:

Rommel Antonio
Operation Head

Noted By:

Rey R. Araos
President